

OFFICE OF THE NAGPUR MUNICIPAL CORPORATION



[GARDEN AND TREE AUTHORITY DEPARTMENT]

Email id : gardendepnt.nmc@gmail.com

P.B.X. No. 84 Civil Lines, Mahanagarpalika Marg, Nagpur-1

No : NMC/GRDN/OWL/2024-25/906

Date :- 3/4/2025

E- QUOTATION NOTICE

E- Quotations NMC Invites Rate For NON CSR ITEM For the Folling Work. These Quotation Can be Submitted by the Enterpreneur Working in this sector of their authorized **Manufacture/Dealer** Quotation Shall be Submitted office before Date :- 10/03/2025 Time 15:00 Pm of the Tree Conservator (Garden Dept.) 6th Floor "C" Wing, NMC Civil Line Nagpur.

NON CSR ITEM

Sr. No	Item Description	Unit	Sr. No	Item Description	Unit
1	<p>Designing, providing and constructing Zipline Single Rope One Way Approx. 130mtr & Operational Equipment etc. complete in adventure park –</p> <p>A. Foundation includes excavation, soiling, pcc, raft, column, tie beam as per drawing etc.</p> <p>B. Fabrication, erection, installation & painting of start tower having provision for Free Fall, Jumaring, Climbing wall & Rappelling wall having L – 4mtr, W – 4mtr, H – 14.5mtr with platform, stairs with foundation & tie backup anchor supports. (Vertical members 150*150*4mm, Horizontal members 100*100*4mm, Cross members 50*50*3mm)</p> <p>C. Supply and installation of certified tested Zipline Cable Aircraft grade GI steel core with accessories like U clamps, Turn buckles, D-Shackles, Thimble etc., all heavy duty.</p> <p>D. Operational equipment to be includes 10 imported certified sets (Zipline Pulleys, Helmet, Harness, Carabiners, Joko), Stopping Pulley, Rope sling 30mtr, Mitton 3pair etc.</p> <p>E. Provide display board (activity name) with metal frame.</p>	<p>Complete Job Work</p> <p>Lumpsum Project Foundation Steel Structure Painting Activity Set up</p>	11	<p>Designing, providing and constructing of closed shed with shutter for trampoline park & soft play area in adventure park having area 25mtr X 14mtr, height 6mtr (Please note separately we required 13mtr * 24mtr closed shed for Trampoline park activity)</p> <p>A. Foundation includes excavation, soiling, filling, pcc, rcc beam, tmt, base plinth slab, fabrication work, GI sheet at top and sides, rolling shutter gate, window frame, roof turbo exhaust fans etc.</p> <p>B. Provide display board (activity name) with metal frame.</p>	<p>Complete Job Work</p> <p>Lumpsum Project Foundation Steel Structure Painting</p>
2	<p>Designing, providing and constructing of adventure play station (High Rope Course) & Operational Equipment etc. complete in adventure park having area 82 feet X 82 feet, length 8mtr X height 6mtr X width 1.5mtr (Having total 12 activities 8mtr each)</p> <p>A. Foundation includes excavation, soiling, pcc, raft, column, as per drawing etc.</p> <p>B. Fabrication, erection, installation & painting of 12 MS Unipoles (CHS OD 219MM X 5MM) having platforms size 1.5mtr X 1.5mtr, platform height approx. 12ft above the ground.</p> <p>C. All 12 unipoles placed in square shape approx. 8 to 10mtrs distance from each other and interconnected to each other with horizontal SHS (72 X 72 X 4MM) members for auto belay system.</p> <p>D. Total 12 numbers activities would be installed in High Rope Course with continues belay system.</p> <p>E. 1 Stairs connecting at one platform to the ground.</p> <p>F. Supply and installation of MS obstacles with certified and tested wire Cable Aircraft grade GI steel core with accessories like U clamps, Turn buckles, D-Shackles, Thimble etc., all heavy duty.</p> <p>G. Operation equipment to be includes 15 imported certified sets (Belay roller Pulleys, Helmet, Harness, Joko, Carabiners etc.)</p> <p>H. Provide display board (activity name) with metal frame.</p>	<p>Complete Job Work</p> <p>Lumpsum Project Foundation Steel Structure Painting Activity Set up</p>	12	<p>Construction of big swing in adventure park having area 6mtr X 2mtr X height 6mtr X width 2mtr (Having total 1 activity)</p> <p>A. Foundation includes excavation, pcc, etc.</p> <p>B. Fabrication, erection, installation & painting of tower in square shape L – 6mtr, W – 2mtr, H – 6mtr (Vertical & Horizontal members 100*100*4mm)</p> <p>C. Provide display board (activity name) with metal frame.</p>	<p>Complete Job Work</p> <p>Lumpsum Project Foundation Steel Structure Painting Activity Set up</p>
3	<p>Designing, providing and constructing Low Rope Course (Tyre crossing, Swinging pole, Dumbel Walk, Drum, Skipping Rope, Horizontal ladder, Rope Bridge, 3 Step Walk, Gladiator rings, Tyre Swing, Tyre bridge, Square walk etc.) at lower level at High rope course (Having total 12 activities 8 meter each)</p> <p>A. Foundation includes excavation, soiling, pcc, raft, column as per drawing etc.</p> <p>B. Fabrication, erection, installation & painting of 12 MS Unipoles (CHS OD 219MM X 5MM) having platforms size 1.5mtr X 1.5mtr, platform height approx. 2.5ft above the ground.</p> <p>C. All 12 unipoles placed in square shape approx. 8 to 10mtrs distance from each other and interconnected to each other with horizontal SHS (72 X 72 X 4MM) members.</p> <p>D. Total 12 numbers activities would be installed in Low Rope Course.</p> <p>E. 1 Stairs connecting at one platform to the ground.</p> <p>F. Supply and installation of MS obstacles with certified and tested wire Cable Aircraft grade GI steel core with accessories like U clamps, Turn buckles, D-Shackles, Thimble etc., all heavy duty.</p> <p>G. Provide display board (activity name) with metal frame.</p>	<p>Complete Job Work</p> <p>Lumpsum Project Foundation Steel Structure Painting Activity Set up</p>	13	<p>Construction of NET climbing in adventure park having length (6mtr X width 3mtr - 2no), (length 6mtr X width 2mtr - 1no) (Having total 3 activities)</p> <p>A. Foundation includes excavation, pcc, etc.</p> <p>B. Fabrication, erection, installation & painting of tower in square shape L – 6mtr, W – 2mtr, H – 6mtr (Vertical & Horizontal members 100*100*4mm)</p> <p>C. Provide display board (activity name) with metal frame.</p>	<p>Complete Job Work</p> <p>Lumpsum Project Foundation Steel Structure Painting Activity Set up</p>

4	<p>Designing, providing and constructing of Climbing wall & Operational Equipment etc. complete in adventure park having Height 12mtr x Width 2mtr with 100 numbers imported climbing holds with anchoring system (Having total 1 activity)</p> <p>A. Supply and installation of certified standard FRP panels with anchoring system with imported Climbing hold 100nos.</p> <p>B. 12 Panels (size L – 1mtr * W – 2mtr) supported on Zipline Tower with MS frames (Vertical & Horizontal members 100*50*3mm).</p> <p>C. 6 imported certified sets of operation gear includes Helmet, Harness, Dynamic Rope 200mtr, Carabiners 6, Descender 2, Chalk Bag with chalk 6 etc.</p> <p>D. Provide display board (activity name) with metal frame.</p>	<p>Complete Job Work</p> <p>Lumpsum Project Foundation Steel Structure Painting Activity Set up</p>	14	<p>Construction of rope climbing in adventure park having height 6mtr X 1mtr (Having total 3 activities)</p> <p>A. Foundation includes excavation, pcc, etc.</p> <p>B. Fabrication, erection, installation & painting of tower in square shape L – 6mtr, W – 2mtr, H – 6mtr (Vertical & Horizontal members 100*100*4mm)</p> <p>C. Provide display board (activity name) with metal frame.</p>	<p>Complete Job Work</p> <p>Lumpsum Project Foundation Steel Structure Painting Activity Set up</p>
5	<p>Designing, providing and constructing of Rappelling wall & Operational Equipment etc. complete in adventure park having Height 12 mtr x Width 2 mtr with anchoring system (Having total 1 activity)</p> <p>A. Supply and installation of certified standard FRP panels with anchoring system.</p> <p>B. 12 Panels (size L – 1mtr * W – 2mtr) supported on Zipline Tower with MS frames.</p> <p>C. 6 imported certified sets of operation gear includes Helmet, Harness, Static Rope 200mtr, Carabiners 10, Descender 4, Mitten pair 6, Single pulley 1.</p> <p>D. Provide display board (activity name) with metal frame.</p>	<p>Complete Job Work</p> <p>Lumpsum Project Foundation Steel Structure Painting Activity Set up</p>	15	<p>Construction of slippery wall in adventure park having length 7mtr X height 3mtr x width 6.5mtr</p> <p>A. Foundation includes excavation, soiling, filling, pcc, murum filling, UCR stone masonry, concreting, plastering, neeru finishing and pointing etc.</p> <p>B. Provide display board (activity name) with metal frame.</p>	<p>Complete Job Work</p> <p>Lumpsum Project Foundation Steel Structure Painting Activity Set up</p>
6	<p>Designing, providing and constructing of bicycle rope way (Sky Cycle Double) & Operational Equipment etc. complete in adventure park having length 80mtr (Having total 2 activities)</p> <p>A. Foundation includes excavation, soiling, pcc, raft, column, tie beam as per drawing etc.</p> <p>B. Fabrication, erection, installation & painting of Start tower of L – 3mtr, W – 6mtr, H – 10mtr with necessary base having stairs & required platform with foundation & tie backup anchor supports. (Vertical members 150*150*4mm, Horizontal members 100*100*4mm, Cross members 50*50*3mm)</p> <p>C. Supply and installation of certified tested Zipline Cable Aircraft grade GI steel core with accessories like U clamps, Turn buckles, D-Shackles, Thimble etc., all heavy duty with modified cycles 2nos etc.</p> <p>D. Operational equipment to be includes imported certified 4 Sets (Pulleys, Helmet, Seat Harness, Carabiners, Joko etc.)</p> <p>E. Provide display board (activity name) with metal frame.</p>	<p>Complete Job Work</p> <p>Lumpsum Project Foundation Steel Structure Painting Activity Set up</p>	16	<p>Provide first aid box in adventure park</p>	<p>Complete Job Work</p> <p>Lumpsum Project</p>
7	<p>Designing, providing and constructing of Sky Roller Double & Operational Equipment etc. complete in adventure park having length 80mtr (Having total 2 activities)</p> <p>A. Foundation includes excavation, soiling, pcc, raft, column, tie beam as per drawing etc.</p> <p>B. Fabrication, erection, installation & painting of Start tower of L – 3mtr, W – 6mtr, H – 10mtr with necessary base having stairs & required platform with foundation & tie backup anchor supports. (Vertical members 150*150*4mm, Horizontal members 100*100*4mm, Cross members 50*50*3mm)</p> <p>C. Supply and installation of certified tested Zipline Cable Aircraft grade GI steel core with accessories like U clamps, Turn buckles, D-Shackles, Thimble etc., all heavy duty with modified sky roller 2nos etc.</p> <p>D. Operational equipment to be includes imported certified 4 Sets (Pulleys, Helmet, Seat Harness, Carabiners, Joko etc.)</p> <p>E. Provide display board (activity name) with metal frame.</p>	<p>Complete Job Work</p> <p>Lumpsum Project Foundation Steel Structure Painting Activity Set up</p>	17	<p>Providing of trained staff to operate the activities and to assist public safety (approx. 11 staff and 1 supervisor) cost for 1 year operations</p>	<p>Complete Job Work</p> <p>Lumpsum Project</p>
8	<p>Designing, providing and constructing Bungee Ejection & Operational Equipment etc. complete in adventure park having area 11mtr X 8mtr, length 9mtr X height 14mtr X width 4mtr (Having 1 activity)</p> <p>A. Supply and installation of Bungee ejection with all the required safety standard.</p> <p>B. On each side of the harness are elastics, which are connected to ropes; the ropes are themselves winding round an electrical hoist. Depending on the rider's weight, the rider gives more or less tension to the elastics. This allows riders from 40 to 110 kg to ride (above 90 kg, an additional elastic is necessary). Then elastics are given tension, and the operator releases the rider by opening the release hook. The rider is propelled to a height that can reach 15 meters. The turnaround time of each ejection is of 2 minute to 3 minute, which allows 20 to 25 riders per hour.</p> <p>C. 6inch PCC for the area of 35ft * 25ft.</p> <p>D. Please note that 3 phase connection require to run this activity.</p> <p>E. Operational equipment to be includes certified Harness 1, Single Pulleys 4, Helmet 1, Swivel 2, Carabiners 8, ejection lock 1, 3 phase motor with gear box 1, tape sling etc.</p> <p>F. Provide display board (activity name) with metal frame.</p>	<p>Complete Job Work</p> <p>Lumpsum Project Foundation Steel Structure Painting Activity Set</p>	18	<p>Maintenance cost such as servicing of equipment, replacement of wear & tear etc. for above mentioned activities, cost for 1 year</p>	<p>Complete Job Work</p> <p>Lumpsum Project</p>

9	Designing, providing and constructing of 1 Suspension bridle & 2 Canopy walk & 1 Burma bridge etc. complete in adventure park having length 30mtr each X height 6mtr X width 1.25mtr (Having total 4 activities) A. Foundation includes excavation, soiling, pcc, raft, column, tie beam as per drawing etc. B. Fabrication, erection, installation & painting of 4 different towers in square shape 30mtr distance from each other of L – 1.25mtr, W – 1.25mtr, H – 6mtr with necessary base having stairs & required platform with foundation & tie backup anchor supports. (Vertical & Horizontal members 100*100*4mm, Cross members 50*50*3mm) C. Supply and installation of certified tested Zipline Cable Aircraft grade GI steel core at the top, bottom and both sides with accessories like U clamps, Turn buckles, D-Shackles, Thimble etc., all heavy duty with required GI pipe planks, MS pipes planks, safety net both side etc. D. Provide display board (activity name) with metal frame.	Complete Job Work Lumpsum Project Foundation Steel Structure Painting Activity Set up	19	Insurance cost for public liability insurance for 1 year	Complete Job Work Lumpsum Project
10	Designing, providing and constructing of trampoline park & soft play area in adventure park having area 32ft X 32ft, height 3mtr (Having multiple activities) A. Incline Trampoline, B. Plain Trampoline, C. Foam pit, D. Wall Climber, E. V Bridge, F. 90 Degree Tunnel, G. Punching Bags, H. Suspension Bridge, I. Zipline, J. Double Roto Slide, K. Animal Climbing Step, L. Sweing, M. Padded Sweing, N. Ball Pool, O. Cross Pathway, P. Belt Tower, Q. Provide display board (activity name) with metal frame etc.	Complete Job Work Lumpsum Project Foundation Steel Structure Painting Activity Set up	20	Insurance cost for staff risk insurance policy for 1 year	Complete Job Work Lumpsum Project

Note:

- 1) These rates will be used for deciding rates/ Estimation purpose only.
- 2) Right to Reject any or all Quotation without issuing any reason is reserved by the municipal G.S. NMC Nagpur.
- 3) Rates Quoted Shall be Excluding GST.
- 4) Rates Shall be quoted for single unit.
- 6) Detailed Description of Items Are Available in the Office of the Garden Superintendent (Garden Dept) NMC Nagpur.
- 7) Last Date Of Submission, 10/03/2025 up to 15.00 Pm
- 8) Opening Date:- 11/03/2025 From 16.00 Pm
- 9) Details of item with pictorial representation are also available on the Website of NMC Nagpur

<https://www.nmcnagpur.gov.in/gardendep/asssets/medifiles/noncsrlist1>

Adv No:

Date:-


Tree Conservator
Nagpur Municipal Corporation, Nagpur